## **Chart 31 Installation Verification**

## **Procedure**

- 1. Verify that all frames are in the proper location per the approved floor plan.
- 2. Verify that all bays are properly secured to the floor and/or overhead support.
- 3. Verify that the framework is properly aligned and plumbed within allowable tolerances.
- 4. Refer to other Installation Sections to equip the frame with fuse panels, equipment shelves and ancillary items.
- 5. STOP. This procedure is complete.